

Ref	Description	Quantity	Unit	Rate	Total
	<u>Preliminaries</u>				
a	Site Set Up & Decamp	1.00	item	£ 1,500.00	£ 1,500.00
	Local Authority Fees				
b	Road Closure Application	0.00	item	£ -	Excluded
c	Road Opening License	0.00	item	£ -	Excluded
d	Lane Rental Charges - Unknown at this stage		item	£ -	Excluded
	Site Accommodation				
e	Delivery of Plant	1.00	Item	£ 750.00	£ 750.00
f	Welfare Facilities - for PC Period	4.00	Week	£ 350.00	£ 1,400.00
g	Collection of Plant	1.00	Item	£ 750.00	£ 750.00
	Management Staff - for PC Period				
h	Site Supervision & Management - Working Foreman	4.00	Week	£ 750.00	£ 3,000.00
i	Commerical Team	4.00	Week	£ 500.00	£ 2,000.00
	Temporary Works				
j	Traffic Management	0.00	Week	£ 1,650.00	Excluded
k	Road Sweeper - for PC Period	4.00	Week	£ 1,500.00	£ 6,000.00
l	Wheel Washing Facilities - Jet Wash		Week	£ -	Excluded
m	Attendant Labour/Gateman /Cleaner		Week	£ -	Excluded
n	Plant, Tools and Equipment	4.00	Week	£ 150.00	£ 600.00
o	Dust Control		Week	£ -	Excluded
p	Setting out Engineer	4.00	visits	£ 750.00	£ 3,000.00
q	WAC Testing		Item		Excluded
r	Test, Clean & CCTV of All Sewers and Drainage	0.00	Item	£ 3,200.00	Excluded
s	As-Built Drawings & Information	1.00	Item	£ 1,250.00	£ 1,250.00
					
	TO SUMMARY				£ 20,250.00

Distinctive Groundworks
LIMITED
CIVIL ENGINEERING CONTRACTORS

Ref	Description	Quantity	Unit	Rate	Total
	<u>SUBSTRUCTUE TO MAIN BUILDING</u> <i>Substructure for foundation to main property as per drawings GA-202 Draft - Jonathan Burlow Architects and 26010 S1.1.1 rev P1 - Foundation Plans Option 1</i>				
	<u>Blockwork</u>				
a	100mm 7N blockwork	10.00	m2	£ 63.00	£ 630.00
b	140mm 7N Blockwork	57.00	m2	£ 91.08	£ 5,191.56
c	140mm 7N Coursing block for sole plate	92.00	m	£ 24.00	£ 2,208.00
d	Concrete upstand - assumed Gen 3	8.00	m3	£ 246.60	£ 1,972.80
e	Shuttering to upstand	97.00	m2	£ 61.00	£ 5,916.61
	<u>Oversite</u> <i>Floor construction as per Constant SD drawing</i>				
f	50mm concrete blinding	264.00	m2	£ 11.13	£ 2,938.32
g	225mm thick Cordek Cellcore HXS	264.00	m2	£ 61.34	£ 16,194.82
h	250mm insitu concrete floor slab - assumed Gen 3	264.00	m2	£ 61.65	£ 16,275.60
i	DPM	264.00	m2	£ 2.40	£ 633.60
j	Reinforcement to slab 40kg/m2	10.56	tonne	£ 2,160.00	£ 22,809.60
k	Light trowel to surface	264.00	m2	£ 5.40	£ 1,425.60
l	Formwork to edge of slab n.e. 250mm deep	114.00	m	£ 18.61	£ 2,121.77
*	<u>Note</u> Insulation and screed - by others				
	<u>Scaffold Base</u>				
m	2m wide crushed concrete scaffold base 150mm thick	228.00	m2	£ 15.57	£ 3,549.96
	TO SUMMARY				£ 81,868.24

Ref	Description	Quantity	Unit	Rate	Total
	<u>DRAINAGE</u>				
 The logo for Distinctive Groundworks Limited is centered across the page. It features the company name 'Distinctive Groundworks' in a large, white, sans-serif font, with a stylized checkmark integrated into the letter 'i' of 'Distinctive'. Below the main name, the words 'LIMITED' and 'CIVIL ENGINEERING CONTRACTORS' are written in a smaller, white, sans-serif font, separated by horizontal lines. LIMITED CIVIL ENGINEERING CONTRACTORS					
	TO SUMMARY				£ -

Ref	Description	Quantity	Unit	Rate	Total
	<u>EXTERNAL WORKS</u>				
 The logo for Distinctive Groundworks Limited is centered across the page. It features the company name 'Distinctive Groundworks' in a large, white, sans-serif font. A white checkmark is integrated into the letter 'i' of 'Distinctive'. Below the company name, the word 'LIMITED' is written in a smaller, white, sans-serif font. Underneath 'LIMITED', the words 'CIVIL ENGINEERING CONTRACTORS' are written in an even smaller, white, sans-serif font. The entire logo is set against a light blue rectangular background that spans the width of the table. Distinctive Groundworks LIMITED CIVIL ENGINEERING CONTRACTORS					
	TO SUMMARY				£ -

Distinctive Groundworks

LIMITED

CIVIL ENGINEERING CONTRACTORS

