

Client: Alex and Emma Collins
Tender Summary: Budget
Foundations and Slab Construction
Foul and Surface Water Drainage
Option 1: Beam and Block



Date: 17th September 2026

Item	Description	Total
1	<u>Foundations and Slab Construction</u> <u>Option2: S1.1.1 P1</u> <u>Concrete foundations, beam and block ground floor and drainage</u>	£ 153,875.13
1.1	Haul road construction	
1.2	Reduced level dig	
	<u>Excavation:</u>	
1.3	Unreinforced concrete pad foundations - as detailed	
1.4	Reinforced concrete strip foundations - as detailed	
1.5	Construction of reinforcement to strip foundations	
1.6	Heave protection installation	
	<u>Concrete pour:</u>	
1.7	To pad and strip foundations	
1.8	Internal drainage	
1.9	Substructure blockwork	
1.10	Beam and block flooring	
	<u>External drainage</u>	
1.11	Foul water drainage	
1.12	Surface water drainage	
1.13	Foul water treatment plant	
1.14	Water harvesting tank	
1.15	Cart away spoil (clay) - as advised	
Total excluding VAT		£ 153,875.13

- Key assumptions & provisional sums**
- a Temporary haul road: to the site location, above ground:
Geotextile layer & 300mm 6f5 material which was originally to be part of the final road construction
 - b Excavation:
Pad foundations and strip foundations - as detailed on engineers drawings
 - c Strip foundations:
500mm wide x 500mm deep - as detailed on engineers drawings
Reinforcement - 40kg/lm - as detailed on engineers drawings
 - d Pad foundations (unreinforced):
1.25m wide x 1.25m wide x 2.1m deep (final depths to suit local geology)
 - e Concrete mix - standard mix included
 - f Heave protection:
to 0.5m depth and 60mm thick to the inside face of the perimeter foundations - as detailed on the engineers drawings
 - g Internal drainage - to the Architects layout design
 - h Substructure blockwork:
To suit beam and block flooring
2 courses of single skin blockwork included
 - j Beam and block flooring
Provisional design undertaken
Floor type - T225mm depth beams with infill blocks

Client: Alex and Emma Collins
Tender Summary: Budget
Foundations and Slab Construction
Foul and Surface Water Drainage
Option 1: Beam and Block



Date: 17th September 2026

Item	Description	Total
k	<u>Foul water drainage:</u> Based upon Architects layout drawing GA-203 - DRAFT Position and types of en-suite bathrooms & WC including connection to treatment plant Increased to 70m 100mm dia drainage and 7No PPIC manholes	
l	<u>Surface water drainage:</u> 25m 100mm dia pipe including 1No PPIC manhole	
m	<u>Foul treatment plant:</u> Finalised - based upon 6 person, including commissioning and electrical connection	
n	Storm water harvesting tank: provisional sum £6,000.00	
o	Cart away: 100m3 of clay	
 <u>Changes to original quotation:</u>		
p	Site haul road can no longer form part of the permanent above ground permeable road design Included within this figure	
q	Beam and block provisional design included - building loadings to be provided	
r	Foul water drainage increased to suit the Architects layout drawings	
s	Foul treatment plant - finalised - 6 person - position to be advised Commissioning included Power supply included - provisional sum (service locations to be determined)	
t	Water harvesting tank included - provisional sum	
u	Cart away 100m3 of as dug clay included	
 <u>Information required:</u>		
v	Substructure foundations - design to be finalised	
w	Foul and surface water drainage - design to be finalised	
x	Beam and block - building loading to be provided to finalise design	
y	Incoming services - details to be provided	
z	Haul road and permeable road design to be reviewed	
 <u>Notes:</u>		
aa	Above ground drainage - further discussion required regarding the viability and necessity of a permeable road considering the gradients and levels of the road and house.	
bb	Installation of an underground water harvesting tank will minimise the amount of surface water requiring disposal (house guttering to harvesting tank)	