

Client: Alex and Emma Collins  
Tender Summary: Budget  
No-dig Specification - Driveway Construction

Date: 17th September 2026



| Item                | Description                                                                                                  | Total       |
|---------------------|--------------------------------------------------------------------------------------------------------------|-------------|
| 1                   | <b><u>Driveway Construction</u></b><br><b><u>Sylvanarb - Tree Protection Plan, ref:- GBL/TSP/2392-02</u></b> | £ 27,402.73 |
| 1.1                 | Remove topsoil                                                                                               |             |
| 1.2                 | Geotextile membrane                                                                                          |             |
| 1.3                 | 4/20mm stone                                                                                                 |             |
| 1.4                 | BodPave                                                                                                      |             |
| 1.5                 | 2/6mm stone                                                                                                  |             |
| 1.6                 | Pegged timber edging boards                                                                                  |             |
| Total excluding VAT |                                                                                                              | £ 27,402.73 |

**Key assumptions & provisional sums**

- a Geotextile membrane:  
Terram TRP 1000
- b 350mm 4/20 angular limestone
- c 40mm BodPave in lieu of permeable block paving
- d 100mm 2/6mm limestone

**Changes to original quotation:**

- e Temporary haul road: to the site location, above ground:  
Geotextile layer & 300mm 6f5 material which was originally included as part of the final road construction which is now included elsewhere
- f No dig driveway construction included

**Notes:**

- g Due to the no-dig permeable road construction being built above existing ground levels to protect tree roots, the building rainwater drainage will be too deep to discharge by gravity into the permeable road system.
- h Alternative solutions - further discussions required regarding construction can be considered and simplified.
- j Temporary haul road can possibly be incorporated into final road design.
- k Ascetics can also be considered when redesigning the road construction.
- l Resulting rainwater can be stored within an underground water harvesting tank and used for external areas and for water within the building.
- m Tree protection fencing is not included
- n Temporary ground protection will be formed by our haul road
- o The use of hand tools to construct the road is impractical our excavator will be implemented for these works