

Client: Alex and Emma Collins
Tender Summary: Budget
8m x 4m - Gym



Ground Bearing Concrete Slab

Date: 17th September 2026

Item	Description	Total
1	<u>Gym Construction</u>	£ 5,770.00
1.1	Remove topsoil	
1.2	Geotextile membrane	
1.3	Subbase - 6f5 stone	
1.4	Construction of concrete slab - shuttering, dpm, chairs & mesh reinforcement	
1.5	Concrete slab pour	
	<u>Key assumptions & provisional sums</u>	
a	<u>Geotextile membrane:</u> Terram TRP 1000	
b	<u>Subbase:</u> 6f5 stone 150mm thick	
c	<u>Construction of concrete slab:</u> DPM, chairs, 2 layers A252 mesh	
d	Drainage - to be advised	
e	Services - to be advised	
	<u>Information required:</u>	
f	Design of the concrete slab - to be advised	
g	Design of the drainage - to be advised	
h	Design of the services - to be advised	